Directorate of Municipal Administration

MGNVY - 2.0

ITEMWISE SCHEDULE-B

Name of the work:-Package-02 Comprehensive development of arterial & sub arterial roads with underground conduits for utilities under Urban connectivity including footpath, drains, drain cover slab at ward nos 2, 3, 10, 15, 16 21, 22, 23, 24, 25, 27, 28, 30, 31, 33, 34, 36, 39, 40, 41, 44, 49, 50, 51, 53, 56, 57 & 58 in Belagavi city corporation limits (DMA/2025-26/RD/WORK_INDENT38534)

Issuded to: Sri. Veerabhadragouda Patil (Prime Contractor), Joint Venture with Infracon Structures Prop. Pramodh Anand

Agreement No.1740586/DMA/TECH/MGNV/12/2025-26/AGR-19 Date:26-02.2026

Contract Amount Rs.428590237.37/-

Head of Account: 4217~60~051~0~06~132~V,
DDO Code:19503D

SNo.	Item Code	Item Name	Unit	Estimate Quantity	After Negotiation Final Quoted Rate in Figure	Amount in Words	Amount in Rs.
1	1.10	Manual Means - Refilling available earth around trenches/pipelines, cables in layers not exceeding 20 cms in depth, compacting Each deposited layer by ramming after watering with a lead upto 50 m, and lift upto 1.5 m. Including cost of all labour complete as per specifications	m^3	28503.23	176.00	Rupees One Hundred Seventy Six Only	5016568.48
2	1.12	Mechanical Means - Earth work in surface excavation by mechanical means for lowering & leveling the ground for all works other than foundation in all kinds of soils & upto depth not exceeding 300mm as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter including dressing of excavated surfaces, disposing off or levelling the excavated earth or sorting & stacking the selected earth for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools, usage of machinery & other appurtenances required to complete the work. In all kinds of soils upto 300 mm depth	m^3	14452.17	101.00	Rupees One Hundred One Only	1459669.17
3	1.14.1	Mechanical Means - Earth work excavation for Foundation by mechanical means for all works & depth upto 3 m, as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, including dressing of excavated surfaces, disposing off or levelling the excavated earth or sorting & stacking the selected earth for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools, usage of machinery & other appurtenaces required to complete the work. In all kinds of soils Depth upto 3 m	m^3	33930.92	112.00	Rupees One Hundred Twelve Only	3800263.04
4	1.17.1	Mechanical Means - Earth work excavation for pipeline trenches in all kinds of soils by mechanical means as per drawing and technical specifications, including setting out, construction of shoring, strutting, barricading, caution lights, bracing, using sight rails & bonding rods at every 100 mm wherever necessary as directed, removal of stumps and other deleterious matter, dressing of sides and levelling the bottom of trench to the extent required , utilising the available excavated earth locally for the work etc., and all other appurtenances complete in the following strata. All kinds of soils. Depth upto 1.50 m	m^3	5171.9400	288.0000	Rupees Two Hundred Eighty Eight Only	1489518.72
5	1.17.2	Mechanical Means - Earth work excavation for pipeline trenches in all kinds of soils by mechanical means as per drawing and technical specifications, including setting out, construction of shoring, strutting, barricading, caution lights, bracing, using sight rails & bonding rods at every 100 mm wherever necessary as directed, removal of stumps and other deleterious matter, dressing of sides and levelling the bottom of trench to the extent required , utilising the available excavated earth locally for the work etc., and all other appurtenances complete in the following strata. Depth exceeding 1.5 m, but not exceeding 3 m	m^3	18892.3300	364.00	Rupees Three Hundred Sixty Four Only	6876808.12
6	1.19.1	Mechanical Means - Earth work excavation for pipeline trenches by mechanical means as per drawing and technical specifications, including setting out, construction of shoring, strutting, barricading, caution lights, bracing, using sight rails & bonding rods at every 100 mm wherever necessary as directed, removal of stumps and other deleterious matter, dressing of sides and levelling the bottom of trench to the extent required , utilising the available excavated earth locally for the work and all other appurtenances to complete in the following strata. Ordinary/soft rock (without requiring blasting) Depth	m^3	451.50	500.00	Rupees Five Hundred Only	225750.00

Seal and Signature of Contractor

CLASS-1 CIVIL CONTRACTOR
DHARWAD

The Executive Enginneer, DMA

SNo.	Item Code	Item Name	Unit	Estimate Quantity	After Negotiation Final Quoted Rate in Figure	Amount in Words	Amount in Rs.
7	1.19.2	Mechanical Means - Earth work excavation for pipeline trenches by mechanical means as per drawing and technical specifications, including setting out, construction of shoring, strutting, barricading, caution lights, bracing, using sight rails & bonding rods at every 100 mm wherever necessary as directed, removal of stumps and other deleterious matter, dressing of sides and levelling the bottom of trench to the extent required , utilising the available excavated earth locally for the work and all other appurtenances to complete in the following strata Depth exceeding 1 5 m, but not exceeding 3 m	m^3	995 00	613 0000	Rupees Six Hundred Thirteen Only	609935 00
8	1 23	Mechanical Means - Providing and Filling in foundation with granite / trap broken metal 100mm and down size & with approved sand including hand packing, ramming, watering, including cost of all materials and labour with all lead and lift complete as per specifications	m^3	369 58	2955 00	Rupees Two Thousand Nine Hundred Fifty Five Only	1092108 90
9	1 8	Manual Means - Construction of Embankment by excavating the available approved Gravel/ Murrum deposited at a place or borrow pits during or prior excavation with all lifts and lead, transportation to site, spreading, grading to required slope and compacting to meet the requirement complete as per specifications, including cost of labour,rolling,water,all materials,usage& all other appurtenaces required to complete the work	m^3	4735 34	522 00	Rupees Five Hundred Twenty Two Only	2471847 48
10	1 9	Manual Means - Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations and other similar works etc in layers not exceeding 20cm in depth, consolidating Each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	m^3	117 34	293 00	Rupees Two Hundred Ninety Three Only	34380 62
11	12 2	Providing weep holes in Brick masonry/Plain/ Reinforced concrete abutment, wing wall/ return wall with PVC Pipe 110mm outer dia at 2 kg per m2, extending through the full width of the structure with slope of 1V :20H towards drawing foce Complete as per drawing and Technical Specifications Ref to MoRT&H IRC - 2706 & 2200	m	459 80	263 00	Rupees Two Hundred Sixty Three Only	120927 40
12	12 2	Providing, lowering, laying, jointing, testing and commissioning of Glazed Stone Ware Pipes of following dia, conforming to IS 651:1992, IS 4127 with latest amendments, including conveying to work site, caulking with hemp dipped in tar and jointing with CM 1:1 5 using OPC, perfect linking and curing for 10 days and testing with water etc with all lead, lifts and as per Technical Specifications The cost to include the cost of all jointing materials, necessary survey works for laying of sewer lines etc complete The contractor will make own arrangements for procuring water for testing 100 mm dia pipes (This is for house service connection only	m	135 00	407 00	Rupees Four Hundred Seven Only	54945 00
13	16 1 1	Providing, lowering, laying, jointing, testing and commissioning of Glazed Stone Ware Pipes of following dia, conforming to IS 651:1992, IS 4127 with latest amendments, including conveying to work site, caulking with hemp dipped in tar and jointing with CM 1:1 5 using OPC, perfect linking and curing for 10 days and testing with water etc with all lead, lifts and as per Technical Specifications The cost to include the cost of all jointing materials, necessary survey works for laying of sewer lines etc complete The contractor will make own arrangements for procuring water for testing 100 mm dia pipes (This is for house service connection only)	m	1156 00	407 00	Rupees Four Hundred Seven Only	470492 00
14	16 1 2	Providing, lowering, laying, jointing, testing and commissioning of Glazed Stone Ware Pipes of following dia, conforming to IS 651:1992, IS 4127 with latest amendments, including conveying to work site, caulking with hemp dipped in tar and jointing with CM 1:1 5 using OPC, perfect linking and curing for 10 days and testing with water etc with all lead, lifts and as per Technical Specifications The cost to include the cost of all jointing materials, necessary survey works for laying of sewer lines etc complete The contractor will make own arrangements for procuring water for testing 150 mm dia pipes	m	2288 00	640 00	Rupees Six Hundred Forty Only	1464320 00

S. S. PATIL
CLASS-1 CIVIL CONTRACTOR
DHARWAD.

SNo.	Item Code	Item Name	Unit	Estimate Quantity	After Negotiation Final Quoted Rate in Figure	Amount in Words	Amount in Rs.
15	16.1.4	Providing, lowering, laying, jointing, testing and commissioning of Glazed Stone Ware Pipes of following dia, conforming to IS 651:1992, IS 4127 with latest amendments, including conveying to work site, caulking with hemp dipped in tar and jointing with CM 1:1.5 using OPC, perfect linking and curing for 10 days and testing with water etc with all lead, lifts and as per Technical Specifications. The cost to include the cost of all jointing materials, necessary survey works for laying of sewer lines etc complete. The contractor will make own arrangements for procuring water for testing.230 mm dia. pipes	m	573.75	971.00	Rupees Nine Hundred Seventy One Only	557111.25
16	16.28	Providing and constructing un-reinforced plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement or any other type as per Clause 1501.2.2 M30 (Grade), coarse and fine aggregates conforming to IS:383:2016:, maximum size of coarse aggregate not exceeding 25 mm, mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including construction joints, primer, sealant, curing of concrete slabs for 14-days, and water finishing to lines and grade as per drawing and technical specification clause 1501 with all lead, lifts, loading & unloading charges, cost and conveyance of all materials, labour, equipments etc., complete as per the directions of the Engineer-in-charge of the work. Ref to MoRT&H : IRC - 1501	m^3	916.82	7442.00	Rupees Seven Thousand Four Hundred Forty Two Only	6822974.44
17	16.28.1	Repairs to Machinehole for different depths including removal of debris, levelling the brick masonry, construction of brick masonry upto Ground level, providing CC coping alround the MH cover, plastering both inside and outside to the brick masonry and fixing of manhole frame and cover, curing, refilling with appurtenances complete. Upto 0.30m depth	each	455.00	9002.00	Rupees Nine Thousand Two Only	4095910.00
18	16.28.3	Repairs to Machinehole for different depths including removal of debris, levelling the brick masonry, construction of brick masonry upto Ground level, providing CC coping alround the MH cover, plastering both inside and outside to the brick masonry and fixing of manhole frame and cover, curing, refilling with appurtenances complete. Upto 0.90m depth	each	22.00	30423.00	Rupees Thirty Thousand Four Hundred Twenty Three Only	669306.00
19	16.40.1	Providing and constructing of Machinehole chambers conical in shape at top with CC 1:3:6 foundation using 40mm and down size graded metal of approved quality and with an offset of 0.15m alround the chamber and brick masonry in C.M 1:4 plaster with bricks of approved quality and CM plaster 1:3 proportion 12mm thick inside and outside except for the conical surface outside where the thickness of plaster shall be 20 mm thick, with 1 to 6 slope in the concrete towards the central drain, finished smooth and fixing of pipes in CC 1:2:4 with graded metal of 20 mm and down size including Providing and fixing SFRC Machinehole frame and cover confoming to IS 12592(Part I): 1988 & IS 12592(Part-II) :1991 with latest amendments in CC 1:2:4, Providing and fixing of plastic foot steps staggered at 30cms apart as directed, watering, curing,barricading, danger lighting, pouring tar over M.H. frame and cover, cost of tar, shoring, strutting, dewatering, engraving Machinehole No. on the inner and outer conical surface etc as per the drawing with all lead and lift for various diameters and depths noted below. With Table Moulded Bricks & Medium Duty cover and frame for 1.2m dia Constructing Table Moulded Bricks Machinehole 1.2m internal dia 1.0 M depth & Medium duty SFRC cover & frame	each	78.00	26831.00	Rupees Twenty Six Thousand Eight Hundred Thirty One Only	2092818.00

V. S. PATIL
CLASS-I CIVIL CONTRACTOR
DHARWAD.

SNo.	Item Code	Item Name	Unit	Estimate Quantity	After Negotiation Final Quoted Rate in Figure	Amount in Words	Amount in Rs.
20	16.40.2	Providing and constructing of Machinehole chambers conical in shape at top with CC 1:3:6 foundation using 40mm and down size graded metal of approved quality and with an offset of 0.15m alround the chamber and brick masonry in C.M 1:4 plaster with bricks of approved quality and CM plaster 1:3 proportion 12mm thick inside and outside except for the conical surface outside where the thickness of plaster shall be 20 mm thick, with 1 to 6 slope in the concrete towards the central drain, finished smooth and fixing of pipes in CC 1:2:4 with graded metal of 20 mm and down size including Providing and fixing SFRC Machinehole frame and cover confoming to IS 12592(Part-I) 1988 & IS 12592(Part-II) :1991 with latest amendments in CC 1:2:4, Providing and fixing of plastic foot steps staggered at 30cms apart as directed, watering, curing,barricading, danger lighting, pouring tar over M.H. frame and cover, cost of tar, shoring, strutting, dewatering, engraving Machinehole No. on the inner and outer conical surface etc as per the drawing with all lead and lift for various diameters and depths noted below. With Table Moulded Bricks & Medium Duty cover and frame For 1.2m dia Constructing Table Moulded Bricks Machinehole 1.2 m internal dia , 2.0 m depth & Medium duty SFRC cover & frame	each	138.00	51192.00	Rupees Fifty One Thousand One Hundred Ninety Two Only	7064496.00
21	16.40.3	Providing and constructing of Machinehole chambers conical in shape at top with CC 1:3:6 foundation using 40mm and down size graded metal of approved quality and with an offset of 0.15m alround the chamber and brick masonry in C.M 1:4 plaster with bricks of approved quality and CM plaster 1:3 proportion 12mm thick inside and outside except for the conical surface outside where the thickness of plaster shall be 20 mm thick, with 1 to 6 slope in the concrete towards the central drain, finished smooth and fixing of pipes in CC 1:2:4 with graded metal of 20 mm and down size including Providing and fixing SFRC Machinehole frame and cover confoming to IS 12592(Part-I): 1988 & IS 12592(Part-II) :1991 with latest amendments in CC 1:2:4, Providing and fixing of plastic foot steps staggered at 30cms apart as directed, watering, curing,barricading, danger lighting, pouring tar over M.H. frame and cover, cost of tar, shoring, strutting, dewatering, engraving Machinehole No. on the inner and outer conical surface etc as per the drawing with all lead and lift for various diameters and depths noted below. With Table Moulded Bricks & Medium Duty cover and frame For 1.2m dia Constructing Table Moulded Bricks Machinehole 1.2 m internal dia , 3.0 M depth & Medium duty SFRC cover & frame	each	51.0000	78326.00	Rupees Seventy Eight Thousand Three Hundred Twenty Six Only	3994626.00
22	16.46.1	Providing and constructing of Machinehole chambers conical in shape at top with CC 1:3:6 foundation using 40mm and down size graded metal of approved quality and with an offset of 0.15m alround the chamber and brick masonry in C.M 1:4 plaster with bricks of approved quality and CM plaster 1:3 proportion 12mm thick inside and outside except for the conical surface outside where the thickness of plaster shall be 20 mm thick, with 1 to 6 slope in the concrete towards the central drain, finished smooth and fixing of pipes in CC 1:2:4 with graded metal of 20 mm and down size including Providing and fixing SFRC Machinehole frame and cover confoming to IS 12592(Part-I): 1988 & IS 12592(Part-II) :1991 with latest amendments in CC 1:2:4, Providing and fixing of plastic foot steps staggered at 30cms apart as directed, watering, curing,barricading, danger lighting, pouring tar over M.H. frame and cover, cost of tar, shoring, strutting, dewatering, engraving Machinehole No. on the inner and outer conical surface etc as per the drawing with all lead and lift for various diameters and depths noted below.Constructing Table Moulded Bricks Machinehole 1.2 m internal dia , 1.5 M depth & Heavy duty SFRC cover & frame (Vol-5 Page No.201 & Item No.16.40)	Each	11.00	39728.00	Rupees Thirty Nine Thousand Seven Hundred Twenty Eight Only	437008.00

V.S.PATIL
CLASS-I CIVIL CONTRACTOR
DHARWAD.

SNo.	Item Code	Item Name	Unit	Estimate Quantity	After Negotiation Final Quoted Rate in Figure	Amount in Words	Amount in Rs.
23	16.46.1	Providing and constructing of Machinehole chambers conical in shape at top with CC 1:3:6 foundation using 40mm and down size graded metal of approved quality and with an offset of 0.15m alround the chamber and brick masonry in C.M 1:4 plaster with bricks of approved quality and CM plaster 1:3 proportion 12mm thick inside and outside except for the conical surface outside where the thickness of plaster shall be 20 mm thick, with 1 to 6 slope in the concrete towards the central drain, finished smooth and fixing of pipes in CC 1:2:4 with graded metal of 20 mm and down size including Providing and fixing SFRC Machinehole frame and cover confoming to IS 12592(Part-I): 1988 & IS 12592(Part-II) :1991 with latest amendments in CC 1:2:4, Providing and fixing of plastic foot steps staggered at 30cms apart as directed, watering, curing,barricading, danger lighting, pouring tar over M.H. frame and cover, cost of tar, shoring, strutting, dewatering, engraving Machinehole No. on the inner and outer conical surface etc. as per the drawing with all lead and lift for various diameters and depths noted below. With Table Moulded Bricks & Heavy Duty cover and frame.For 1.2m dia Constructing Table Moulded Bricks Machinehole 1.2 m internal dia. , 1.0 M depth & Heavy duty SFRC cover & frame	each	42.00	27548.00	Rupees Twenty Seven Thousand Five Hundred Forty Eight Only	1157016.00
24	16.46.1	Providing and constructing of Machinehole chambers conical in shape at top with CC 1:3:6 foundation using 40mm and down size graded metal of approved quality and with an offset of 0.15m alround the chamber and brick masonry in C.M 1:4 plaster with bricks of approved quality and CM plaster 1:3 proportion 12mm thick inside and outside except for the conical surface outside where the thickness of plaster shall be 20 mm thick, with 1 to 6 slope in the concrete towards the central drain, finished smooth and fixing of pipes in CC 1:2:4 with graded metal of 20 mm and down size including Providing and fixing SFRC Machinehole frame and cover confoming to IS 12592(Part-I): 1988 & IS 12592(Part-II) :1991 with latest amendments in CC 1:2:4, Providing and fixing of plastic foot steps staggered at 30cms apart as directed, watering, curing,barricading, danger lighting, pouring tar over M.H. frame and cover, cost of tar, shoring, strutting, dewatering, engraving Machinehole No. on the inner and outer conical surface etc. as per the drawing with all lead and lift for various diameters and depths noted below.Constructing Table Moulded Bricks Machinehole 1.2 m internal dia. , 1.2 M depth & Heavy duty SFRC cover & frame (Vol-5 Page No.201 & Item No.16.46.1)	Each	13.00	32420.00	Rupees Thirty Two Thousand Four Hundred Twenty Only	421460.00
25	16.46.2	Providing and constructing of Machinehole chambers conical in shape at top with CC 1:3:6 foundation using 40mm and down size graded metal of approved quality and with an offset of 0.15m alround the chamber and brick masonry in C.M 1:4 plaster with bricks of approved quality and CM plaster 1:3 proportion 12mm thick inside and outside except for the conical surface outside where the thickness of plaster shall be 20 mm thick, with 1 to 6 slope in the concrete towards the central drain, finished smooth and fixing of pipes in CC 1:2:4 with graded metal of 20 mm and down size including Providing and fixing SFRC Machinehole frame and cover confoming to IS 12592(Part-I): 1988 & IS 12592(Part-II) :1991 with latest amendments in CC 1:2:4, Providing and fixing of plastic foot steps staggered at 30cms apart as directed, watering, curing,barricading, danger lighting, pouring tar over M.H. frame and cover, cost of tar, shoring, strutting, dewatering, engraving Machinehole No. on the inner and outer conical surface etc. as per the drawing with all lead and lift for various diameters and depths noted below.Constructing Table Moulded Bricks Machinehole 1.2 m internal dia. , 2.8 M depth & Heavy duty SFRC cover & frame (Vol-5 Page No.201 & Item No.16.40)	Each	5.00	73500.00	Rupees Seventy Three Thousand Five Hundred Only	367500.00

N. S. PATIL
CLASS-1 CIVIL CONTRACTOR
DHARWAD.

Seal and Signature of Contractor

The Executive Engineer, DMA

SNo.	Item Code	Item Name	Unit	Estimate Quantity	After Negotiation Final Quoted Rate in Figure	Amount in Words	Amount in Rs.
26	16.46.2	Providing and constructing of Machinehole chambers conical in shape at top with CC 1:3:6 foundation using 40mm and down size graded metal of approved quality and with an offset of 0.15m alround the chamber and brick masonry in C.M 1:4 plaster with bricks of approved quality and CM plaster 1:3 proportion 12mm thick inside and outside except for the conical surface outside where the thickness of plaster shall be 20 mm thick, with 1 to 6 slope in the concrete towards the central drain, finished smooth and fixing of pipes in CC 1:2:4 with graded metal of 20 mm and down size including Providing and fixing SFRC Machinehole frame and cover confoming to IS 12592(Part-I): 1988 & IS 12592(Part-II) :1991 with latest amendments in CC 1:2:4, Providing and fixing of plastic foot steps staggered at 30cms apart as directed, watering, curing,barricading, danger lighting, pouring tar over M.H. frame and cover, cost of tar, shoring, strutting, dewatering, engraving Machinehole No. on the inner and outer conical surface etc. as per the drawing with all lead and lift for various diameters and depths noted below.Constructing Table Moulded Bricks Machinehole 1.2 m internal dia , 2.5 M depth & Heavy duty SFRC cover & frame (Vol-5 Page No.201 & Item No.16.40)	Each	5.00	65476.00	Rupees Sixty Five Thousand Four Hundred Seventy Six Only	327380.00
27	16.46.2	Providing and constructing of Machinehole chambers conical in shape at top with CC 1:3:6 foundation using 40mm and down size graded metal of approved quality and with an offset of 0.15m alround the chamber and brick masonry in C.M 1:4 plaster with bricks of approved quality and CM plaster 1:3 proportion 12mm thick inside and outside except for the conical surface outside where the thickness of plaster shall be 20 mm thick, with 1 to 6 slope in the concrete towards the central drain, finished smooth and fixing of pipes in CC 1:2:4 with graded metal of 20 mm and down size including Providing and fixing SFRC Machinehole frame and cover confoming to IS 12592(Part-I): 1988 & IS 12592(Part-II) :1991 with latest amendments in CC 1:2:4, Providing and fixing of plastic foot steps staggered at 30cms apart as directed, watering, curing,barricading, danger lighting, pouring tar over M.H. frame and cover, cost of tar, shoring, strutting, dewatering, engraving Machinehole No. on the inner and outer conical surface etc. as per the drawing with all lead and lift for various diameters and depths noted below.Constructing Table Moulded Bricks Machinehole 1.2 m internal dia , 2.2 M depth & Heavy duty SFRC cover & frame (Vol-5 Page No.201 & Item No.16.40)	Each	4.00	57336.00	Rupees Fifty Seven Thousand Three Hundred Thirty Six Only	229344.00
28	16.46.2	Providing and constructing of Machinehole chambers conical in shape at top with CC 1:3:6 foundation using 40mm and down size graded metal of approved quality and with an offset of 0.15m alround the chamber and brick masonry in C.M 1:4 plaster with bricks of approved quality and CM plaster 1:3 proportion 12mm thick inside and outside except for the conical surface outside where the thickness of plaster shall be 20 mm thick, with 1 to 6 slope in the concrete towards the central drain, finished smooth and fixing of pipes in CC 1:2:4 with graded metal of 20 mm and down size including Providing and fixing SFRC Machinehole frame and cover confoming to IS 12592(Part-I): 1988 & IS 12592(Part-II) :1991 with latest amendments in CC 1:2:4, Providing and fixing of plastic foot steps staggered at 30cms apart as directed, watering, curing,barricading, danger lighting, pouring tar over M.H. frame and cover, cost of tar, shoring, strutting, dewatering, engraving Machinehole No. on the inner and outer conical surface etc. as per the drawing with all lead and lift for various diameters and depths noted below. With Table Moulded Bricks & Heavy Duty cover and frame.For 1.2m dia Constructing Table Moulded Bricks Machinehole 1.2 m internal dia , 2.0 m depth & Heavy duty SFRC cover & frame	each	10.00	51909.00	Rupees Fifty One Thousand Nine Hundred Nine Only	519090.00
29	17.14	Providing and laying 100mm thick pre-cast cover slabs over Road side drains / utility ducts / Rain water harvesting pit of width not exceeding 1000 mm using M20 concrete reinforced with TMT bars Fe 550 @ 6kg/ m2, slabs jointed in CM 1:3 proportion and nicely finished Including providing holes in the Cover slabs wherever necessary for easy drain- age of surface water including of labour, materials, scaffolding, usage of machinery, curing, lead and lift charges etc. Complete	m^2	10321.42	1289.00	Rupees One Thousand Two Hundred Eighty Nine Only	13304310.38

S.PATIL
CLASS-1 CIVIL CONTRACTOR
DHARWAD.

SNo.	Item Code	Item Name	Unit	Estimate Quantity	After Negotiation Final Quoted Rate in Figure	Amount in Words	Amount in Rs.
30	2.1.3	Providing and laying in position Cement Concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machinery, curing, and all the other appurtenances required to complete the work as per technical specifications. - Mix 1:3:6 Using 40 mm nominal size graded crushed coarse aggregates	m^3	1536.78	6599.00	Rupees Six Thousand Five Hundred Ninety Nine Only	10141211.22
31	2.1.6	Providing and laying in position Cement Concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machinery, curing, and all the other appurtenances required to complete the work as per technical specifications. - Mix 1:2:4 Using 20 mm nominal size graded crushed coarse aggregates	m^3	262.95	6879.00	Rupees Six Thousand Eight Hundred Seventy Nine Only	1808833.05
32	2.11.h	Steel Fabrication Supplying, fitting and placing TMT FE 550 / 550D Steel Reinforcement including cost of all materials, machinery, labour, cleaning, straightening, cutting, bending, hooking, laping/welding joints, tying with binding wire / soft annealed steel wire and other ancilary operations complete as per drawing and technical specification. All other type of structures	t	396.97	87068.00	Rupees Eighty Seven Thousand Sixty Eight Only	34563383.96
33	2.19	Dismantling of Cement Concrete Pavement - Dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 m3 in volume and stock piling at designated locations and disposal of dismantled materials and stacking serviceable and unserviceable materials separately. Ref to MoRT&H : IRC - 202	m^3	220.25	620.00	Rupees Six Hundred Twenty Only	136555.00
34	2.3.1	Providing and laying in Cement Concrete for all Basement & surface level works, return walls, retaining walls, sunken floors etc The granite/trap/ basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necessary, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. - M 20 Design Mix Using 20 mm nominal size graded crushed coarse aggregates	m^3	20.7200	6639.00	Rupees Six Thousand Six Hundred Thirty Nine Only	137560.08
35	2.4.2	Providing and laying in position Cement Concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necessary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. - M 20 Design Mix Using 20 mm nominal size graded crushed coarse aggregates	m^3	1424.47	7300.00	Rupees Seven Thousand Three Hundred Only	10398631.00
36	2.4.2	Providing and laying in position Cement Concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necessary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. - M 20 Design Mix Using 20 mm nominal size graded crushed coarse aggregates	m^3	23.32	8361.00	Rupees Eight Thousand Three Hundred Sixty One Only	194978.52

V. S. PATIL
CLASS-I CIVIL CONTRACTOR
DHARWAD.

Seal and Signature of Contractor

The Executive Engineer, DMA

SNo.	Item Code	Item Name	Unit	Estimate Quantity	After Negotiation Final Quoted Rate in Figure	Amount in Words	Amount in Rs.
37	2.4.2	Providing and laying in position Cement Concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necessary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications - M 20 Design Mix Using 20 mm nominal size graded crushed coarse aggregates	m^3	45.84	6967.00	Rupees Six Thousand Nine Hundred Sixty Seven Only	319367.28
38	2.4.2	Providing and laying in position Cement Concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necessary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications - M 20 Design Mix Using 20 mm nominal size graded crushed coarse aggregates	m^3	2029.46	9406.00	Rupees Nine Thousand Four Hundred Six Only	19089100.76
39	2.4.2	Providing and laying in position Cement Concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necessary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications - M 20 Design Mix Using 20 mm nominal size graded crushed coarse aggregates	m^3	5.76	7525.00	Rupees Seven Thousand Five Hundred Twenty Five Only	43344.00
40	2.4.3	Providing and laying in position Cement Concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necessary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications - M 25 Design Mix Using 20 mm nominal size graded crushed coarse aggregates	m^3	92.18	7300.00	Rupees Seven Thousand Three Hundred Only	672914.00
41	2.4.3	Providing and laying in position Cement Concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necessary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications - M 25 Design Mix Using 20 mm nominal size graded crushed coarse aggregates	m^3	824.65	9300.00	Rupees Nine Thousand Three Hundred Only	7669245.00
42	2.4.3	Providing and laying in position Cement Concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necessary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications M25 Design Mix Using 20 mm nominal size graded crushed coarse aggregates (SR 2023-24 (Vol-1 Page No 16 & Item No 2.4.3)	Cum	19.17	8378.00	Rupees Eight Thousand Three Hundred Seventy Eight Only	160606.26

CLASS-I CIVIL CONTRACTOR
DHARWAD.

SNo.	Item Code	Item Name	Unit	Estimate Quantity	After Negotiation Final Quoted Rate in Figure	Amount in Words	Amount in Rs.
43	2.4.3	Providing and laying in position Cement Concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necessary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. - M 25 Design Mix Using 20 mm nominal size graded crushed coarse aggregates	m^3	227.29	6982.00	Rupees Six Thousand Nine Hundred Eighty Two Only	1586938.78
44	2.5.1	Providing and laying in position Cement Concrete for all Super structures of building , Road works, Water works, Irrigation works & super structure works of bridges upto 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers laid in layers, well compacted using needle vibrators. The cost includes all lead & lifts, cost of all materials, quality confirming to the requirements of relevant IS codes , labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. - M 20 Design Mix Using 20 mm nominal size graded crushed coarse aggregates	m^3	42.78	7306.00	Rupees Seven Thousand Three Hundred Six Only	312550.68
45	2.5.3	Providing and laying in position Cement Concrete for all Super structures of building , Road works, Water works, Irrigation works & super structure works of bridges upto 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers laid in layers, well compacted using needle vibrators. The cost includes all lead & lifts, cost of all materials, quality confirming to the requirements of relevant IS codes , labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. - M 30 Design Mix Using 20 mm nominal size graded crushed coarse aggregates	m^3	227.11	9265.00	Rupees Nine Thousand Two Hundred Sixty Five Only	2104174.15
46	2.5.ii.a	Clearing and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable material to be used or auctioned, including removal and disposal of top organic soil not exceeding 150 mm in thickness. By Mechanical Means using Dozer - In area of light jungle	100 m2	122.90	433.00	Rupees Four Hundred Thirty Three Only	53215.70
47	2.8.ii.a	Dismantling of Structures - Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead - Lime /Cement Concrete - By Mechanical Means - Cement Concrete Grade M-15 & M-20	m^3	814.17	792.00	Rupees Seven Hundred Ninety Two Only	644822.64
48	3.1	Removal of Unserviceable Soil with Disposal upto a suitable distance as directed by the Engineer incharge of work. Ref to MoRT&H - IRC - 301	m^3	9920.29	93.00	Rupees Ninety Three Only	922586.97
49	3.6	Construction of Subgrade and Earthen Shoulders - Construction of sub-grade and earthen shoulders with approved material obtained from borrow pits with all lifts & leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of table No. 300-2. Ref to MoRT&H - IRC - 305	m^3	2133.76	540.00	Rupees Five Hundred Forty Only	1152230.40
50	3.7	Compacting Original Ground - Compacting original ground supporting embankment - Loosening, leveling and Compacting original ground supporting embankment to facilitate placement of first layer of embankment, scarified to a depth of 150 mm, mixed with water at OMC and then compacted by rolling so as to achieve minimum dry density as given in Table 300-2 for embankment construction. Ref to MoRT&H - IRC - 305.3.4	m^3	926.50	115.00	Rupees One Hundred Fifteen Only	106547.50
51	4.1.A.iv	Granular Sub-Base - Plant Mix Method - Construction of Granular Sub-Base of required grading as per design mixing in a mechanical mix plant at OMC, carriage of mixed Material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per clause 401 - For Grading -IV Material Ref to MoRT&H - IRC - 401	m^3	2873.76	2774.00	Rupees Two Thousand Seven Hundred Seventy Four Only	7971810.24

V.S. PATIL
CLASS-I CIVIL CONTRACTOR
DHARWAD.

SNo.	Item Code	Item Name	Unit	Estimate Quantity	After Negotiation Final Quoted Rate in Figure	Amount in Words	Amount in Rs.
52	4 1 A vi	Granular Sub-Base - Plant Mix Method - Construction of Granular Sub-Base of required grading as per design mixing in a mechanical mix plant at OMC, carriage of mixed Material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per clause 401 - For Grading -VI Material Ref to MoRT&H : IRC - 401	m^3	121.25	2791.00	Rupees Two Thousand Seven Hundred Ninety One Only	338408.75
53	4.17	Wet Mix Macadam (Plant Mix Method) - Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver/grader in sub-base / base course on well prepared surface and compacting with vibratory rollerto achieve the desireddensity Ref to MoRT&H : IRC - 406	m^3	15580.17	2781.00	Rupees Two Thousand Seven Hundred Eighty One Only	43328452.77
54	4 2 B iv	Granular Sub-Base - By Mix in Place Method - Construction of Granular Sub-Base of required grading as per design spreading in uniform layers with motor grader on prepared surface mixing by mix in place method with front end loader at OMC and compacting with vibratory roller to achieve the desired density, complete as per clause 401 - For Grading -IV Material Ref to MoRT&H : IRC - 401	m^3	437.32	2550.00	Rupees Two Thousand Five Hundred Fifty Only	1115166.00
55	5 1 A i	Prime Coat over WMM/WBM - Providing and applying primer coat with SS1 grade Bitumen Emulsion on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70 kg/m2 using mechanical means Ref to MoRT&H : IRC - 502	m^2	53847.50	45.00	Rupees Forty Five Only	2423137.50
56	5 12 C	Dense Graded Bituminous Macadam Grading - II for traffic <20 MSA - Providing and laying Dense Graded Bituminous Macadam with 40/60 TPH capacity HMP using crushed aggregates of specified grading, premixed with bituminous binder VG-30, @ 4.5 per cent by weight of total mix and filler, transporting the hot mix to work site, laying with mechanical paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRTH specification clause No 505 complete in all respects Ref to MoRT&H : IRC - 505	m^3	4807.69	10412.00	Rupees Ten Thousand Four Hundred Twelve Only	50057668.28
57	5 16 B C	Bituminous Concrete Grading II for traffic <20 MSA - Providing and laying Bituminous Concrete with 40/60 TPH capacity hot mix plant using crushed aggregates of specified grading, premixed with bituminous binder VG-30, @ 5.4 per cent of mix and filler, transporting the hot mix to work site, laying with mechanical paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 507 complete in all respects Ref to MoRT&H : IRC - 507	m^3	2871.29	12071.00	Rupees Twelve Thousand Seventy One Only	34659341.59
58	5 3 i	Tack coat on Bituminous surface - Providing and applying tack coat with RS1 Bituminous Emulsion using emulsion pressure distributor at the rate of 0.20 kg/m2 on the prepared bituminous surface cleaned with mechanical broom Ref to MoRT&H : IRC - 503	m^2	95582.00	13.00	Rupees Thirteen Only	1242566.00
59	6 8 1	Precast Cement Concrete Interlocking Blocks - Providing and laying 60mm thick factory made precast M -30 grade Cement Concrete Paver Block as per IRC SP 63:2018 & IS 15658 for Cycle Tracks & Pedestrian Footpaths of approved shape and colour, laid in required pattern and including over 30mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in- charge (WMM/WBM Base to be paid separately if necessary as per relevant technical specification) Ref to MoRT&H : IRC - IRC SP 63:2018	m^2	250.00	1176.00	Rupees One Thousand One Hundred Seventy Six Only	294000.00
60	6 8 2	Precast Cement Concrete Interlocking Blocks - Providing and laying 80mm thick factory made precast M -30 grade Cement Concrete Paver Block as per IRC SP 63:2018 & IS 15658 for Commercial Traffic Axle load repetitions upto 10MSA & for Residential Streets of approved shape and colour, laid in required pattern and including over 40mm thick compacted bed of coarse sand, filling the joints with fine sand etc all complete as per the direction of Engineer-in-charge (WMM/WBM Base to be paid separately as per relevant technical specification) Ref to MoRT&H : IRC - IRC SP 63:2018	m^2	24495.20	1287.00	Rupees One Thousand Two Hundred Eighty Seven Only	31525322.40

V. S. PATIL
CLASS-1 CIVIL CONTRACTOR
DHARWAD

Seal and Singnature of Contractor

The Executive Engineer, DMA

SNo.	Item Code	Item Name	Unit	Estimate Quantity	After Negotiation Final Quoted Rate in Figure	Amount in Words	Amount in Rs.
61	8.1.a	Cast in Situ Cement Concrete M20 Kerb - Construction of cement concrete kerb with top and bottom width 115 and 165 mm respectively, 250 mm high in M 15 grade foundation 150 mm thick, foundation having 50 mm projection beyond kerb stone, kerb stone laid with kerb laying machine, foundation concrete laid manually, all complete as per clause 409 - PCC M15 grade for kerb base. Ref to MoRT&H : IRC - 409	m	342.00	263.00	Rupees Two Hundred Sixty Three Only	89946.00
62	8.15	Road Marking with Hot Applied Thermoplastic Compound with Reflectorising Glass Beads on Bituminous Surface - Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 g/m2 area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35:2015 The finished surface to be level, uniform and free from streaks and holes. Ref to MoRT&H : IRC - 803	m^2	3925.35	550.00	Rupees Five Hundred Fifty Only	2158942.50
63	8.42.1	Kerb Stones - Supplying and fixing M15 grade precast cement concrete Kerb stones for Roadway, Sidewalls and gutters fixed with CM 1:3 fixed and finsihed in line as per direction of Engineer in charge. (The cost of PCC shall be paid extra) - 300 x 250 x 100 mm size	m	300.00	333.00	Rupees Three Hundred Thirty Three Only	99900.00
64	8.42.8	Kerb Stones - Supplying and fixing M15 grade precast cement concrete Kerb stones for Roadway, Sidewalls and gutters fixed with CM 1:3 fixed and finsihed in line as per direction of Engineer in charge. (The cost of PCC shall be paid extra) - 300 x 200 x 150 mm size	m	100.00	370.00	Rupees Three Hundred Seventy Only	37000.00
65	8.43	Supplying and Fixing of Molded Shank Raised Pavement Markers / Cats Eye made of polycarbonate and ABS moulded body and reflective panels with micro prismatic lens capable of providing total internal reflection of the light entering the lens face and shall support a load of 16000 kg tested in accordance to ASTM D 4280 Type H and complying to Specifications of Category A of MORTH Circular No RW/NH/33023/10-97 DO III Dt 11.06.1997. The height, width and length shall not exceed 50 mm, 100 mm and 102 +/- 2 mm and with minimum reflective area of 13 cm2 on each side and the slope to the base shall be 35 +/- 5 degree. The strength of detachment of the integrated cylindrical shanks, (of diameter not less than 19 +/- 2 mm and height not less than 30+/- 2 mm) from the body is to be a minimum value of 500 Kg. Fixing will be by drilling holes on the road for the shanks to go inside, without nails and using epoxy resin based adhesive as per manufacturers recommendation and complete as directed by the engineer.The contractor shall submit a two year warranty for satisfactory field performance including stipulated retro-reflectance of the reflecting panel, to the Engineer. Ref to MoRT&H : IRC - MoRTH 806	No.	1462.00	402.00	Rupees Four Hundred Two Only	587724.00
66	8.5.iv	Retro-Reflectorised Traffic Signs - Providing and fixing of retro-reflectorised cautionary, mandatory and informatory sign as per IRC:67:2022 made of Class B Type IV retro reflective sheeting fixed over 2 mm thick aluminium sheeting vide clause 803.1, 3mm/4mm thick Aluminium composite material sheet depending on the size of the sign fixed over the back support frame of min 25 x 25 x 3mm angle mounted on a mild steel circular pipe 65 NB, 3.2 mm thickness firmly fixed to the ground by means of properly designed foundation with M25 grade cement concrete 45 cm x 45 cm x 60 cm, 60 cm below ground level as per approved drawing.The sign shall be maintained as per section 12 of IRC:67:2022 - 60 cm equilateral triangle. Ref to MoRT&H : IRC - 801	each	88.00	3940.00	Rupees Three Thousand Nine Hundred Forty Only	346720.00
67	8.54	Providing and fixing board displaying information, such as Name of work, Tender cost, Name of Contractor, Work completion and liability period etc, having rectangular shape of 1.20m x 0.90m size made out 18 gauge (1.25mm) thick mild steel sheet painted with one coat of Zinc chromate stoving primer and two coats of enamel paint on front side and grey stove enamel on back side and border / messages / symbols etc with approved colour shade paint complete, on M.S angle of size 35 x 35 x 3 mm frame with properly cross braced M.S. angles of size 35mmx35mmx3mm duly painted including Two M.S. angle iron posts of size 65 mm x 65 mm x 6 mm, 3.65 m long painted with alternate black and white bands of 25 cm width including all fixtures etc and fixing the boards in 1:4:8 concrete block of size 60 cm x 60 cm x 75 cm including, excavation, refilling, transportation, and labour etc complete Spec. No. As directed by Engineer in Charge & MoRTH specification 804. Ref to MoRT&H : IRC : MoRTH 804	No.	392.55	9917.00	Rupees Nine Thousand Nine Hundred Seventeen Only	3892918.35

CLASS-I CIVIL CONTRACTOR

SNo.	Item Code	Item Name	Unit	Estimate Quantity	After Negotiation Final Quoted Rate in Figure	Amount in Words	Amount in Rs.
68	8 60 1 i	Pedestrian Crossings as per IRC 99-2018 - Providing Speed Breakers/Raised pedestrian crossings in Trapezoidal section with 2 5 m Top width and transition length of 0 8 m length and height of 0 1 m as per IRC 99:2018 using Bituminous Macadam (BM) Gr II and Semi Dense Bituminous Macadam (SDBC) Gr II for entire formation width & WBM Gr II for Shoulder hump portion only (150 mm thick). completing with road marking paint with applied thermoplastic compound with reflecting glass beeds on bituminous surface and providing 2 Nos. retro reflective traffic signs as per IRC 67 -2022 - Single lane with formation width of 5 75 m. Ref to MoRT&H : IRC - IRC 99 : 2018	No.	4 00	38491 00	Rupees Thirty Eight Thousand Four Hundred Ninety One Only	153964 00
69	8.8	Direction and Place Identification Signs with size more than 0 9 m2 size Board - Providing and erecting direction and place identification retro- reflectorised sign as per IRC:67:2022 made of high intensity grade sheeting vide clause 801 3, fixed over aluminium sheeting, 2 mm thick or Aluminium composite material sheet with overall thickness of 4mm with area exceeding 0 9 m2 fixed over back support frame of min 40 x 40 x 5mm angle mounted on a mild steel circular pipe 65 NB, firmly fixed to the ground by means of properly designed foundation with M25 grade cement concrete 45 x 45 x 60 cm, 60 cm below ground level as per approved drawing. Ref to MoRT&H : IRC - 801	m^2	10 85	10691 00	Rupees Ten Thousand Six Hundred Ninety One Only	115997 35
70	8 9 A	Overhead Signs - Providing and erecting overhead signs with a corrosion resistant 2mm thick aluminium alloy sheet reflectorised with high intensity retro-reflective sheeting as per IRC:67 2022 with vertical and lateral clearance given in clause 802 2 and 802 3 and installed as per clause 802 7 over a designed support system of aluminium alloy or galvanised steel trestles and trusses of sections and type as per structural design requirements and approved plans - Truss and Vertical Support Ref to MoRT&H : IRC - 802	t	9 97	95350 00	Rupees Ninety Five Thousand Three Hundred Fifty Only	950639 50
71	8 9 B	Overhead Signs - Providing and erecting overhead signs with a corrosion resistant 2mm thick aluminium alloy sheet reflectorised with high intensity retro-reflective sheeting as per IRC:67 2022 with vertical and lateral clearance given in clause 802 2 and 802 3 and installed as per clause 802 7 over a designed support system of aluminium alloy or galvanised steel trestles and trusses of sections and type as per structural design requirements and approved plans - Aluminium Alloy Plate for Over Head Sign. Ref to MoRT&H : IRC - 802	m^2	72 00	6411 00	Rupees Six Thousand Four Hundred Eleven Only	461592.00
72	9 1 4	Providing, laying and jointing HDPE pipes of specified grade and conforming to IS 4984-2016 with latest ammendments and conveying to work site including loading and unloading at both destinations and rolling and lowering into trenches, laying true to line and jointing of pipes and specials with electrofusion welding, giving hydraulic test as per relevant ISS with all lead and lifts including encasing the pipe allround to a depth of not less than 15 cms. with soft gravel or selected earth available from the excation, testing and commissioning. The rate is exclusive of required specials and fittings wherever necessary like saddle Tee, stub ends, flanged sets, bends, reducers etc complete (Contractor will make his own arrangements for procuring water for testing) etc complete. NOTE: Upto 110mm dia Coil shall be used. For :HDPE PE 80 PN 6.0 - HDPE Grade PE80-PN6.0,110mm dia	m	45398 80	470 00	Rupees Four Hundred Seventy Only	21337436 00

N.S. PATIL
CLASS-I CIVIL CONTRACTOR
DHARWAD.

SNo.	Item Code	Item Name	Unit	Estimate Quantity	After Negotiation Final Quoted Rate in Figure	Amount in Words	Amount in Rs.
73	9.1.9	Providing, laying and jointing HDPE pipes of specified grade and conforming to IS 4984-2016 with latest ammendments and conveying to work site including loading and unloading at both destinations and rolling and lowering into trenches, laying true to line and jointing of pipes and specials with electrofusion welding, giving hydraulic test as per relevant ISS with all lead and lifts including encasing the pipe alround to a depth of not less than 15 cms. with soft gravel or selected earth available from the excation, testing and commissioning. The rate is exclusive of required specials and fittings wherever necessary like saddle Tee, stub ends, flanged sets, bedns, reducers etc. complete (Contractor will make his own arrangements for procuring water for testing) etc. complete. NOTE: Upto 110mm dia Coil shall be used. For HDPE PE 80 PN 6.0 - HDPE Grade PE80-PN6.0,200mm dia	m	22699.40	1500.00	Rupees One Thousand Five Hundred Only	34049100.00
74	9.16.10	Providing and installation of Class SN8 Double Wall Corrugated HDPE pipe outer wall corrugated and inner wall smooth piping system in accordance with IS 16098 part 2 and conveying to work site and lowering into trenches, laying true to line and level and perfect linking at joints with the help of two O rings and a coupler of suitable size, including loading and unloading at both destination and cutting of pipes where ever necessary including jointing with all labour, all lead and lift including encasing the pipe around to a depth of not less than 15 cm with screened soft soil available from the excavated soil. The testing commissioning including necessary hydraulic test to the required pressure as per ISS shall be done the contractor shall have to make his own arrangement for procuring water for testing etc. complete. SN8 Double Wall Corrugated HDPE pipe sizes of 600 mm dia	m	1700.00	6406.00	Rupees Six Thousand Four Hundred Six Only	10890200.00
75	9.16.6	Providing and installation of Class SN8 Double Wall Corrugated HDPE pipe outer wall corrugated and inner wall smooth piping system in accordance with IS 16098 part 2 and conveying to work site and lowering into trenches, laying true to line and level and perfect linking at joints with the help of two O rings and a coupler of suitable size, including loading and unloading at both destination and cutting of pipes where ever necessary including jointing with all labour, all lead and lift including encasing the pipe around to a depth of not less than 15 cm with screened soft soil available from the excavated soil. The testing commissioning including necessary hydraulic test to the required pressure as per ISS shall be done the contractor shall have to make his own arrangement for procuring water for testing etc. complete. SN8 Double Wall Corrugated HDPE pipe sizes of 250 mm dia	m	3462.00	1244.00	Rupees One Thousand Two Hundred Forty Four Only	4306728.00
76	9.16.7	Providing and installation of Class SN8 Double Wall Corrugated HDPE pipe outer wall corrugated and inner wall smooth piping system in accordance with IS 16098 part 2 and conveying to work site and lowering into trenches, laying true to line and level and perfect linking at joints with the help of two O rings and a coupler of suitable size, including loading and unloading at both destination and cutting of pipes where ever necessary including jointing with all labour, all lead and lift including encasing the pipe around to a depth of not less than 15 cm with screened soft soil available from the excavated soil. The testing commissioning including necessary hydraulic test to the required pressure as per ISS shall be done the contractor shall have to make his own arrangement for procuring water for testing etc. complete. SN8 Double Wall Corrugated HDPE pipe sizes of 300 mm dia	m	2368.00	1655.00	Rupees One Thousand Six Hundred Fifty Five Only	3919040.00
77	No.07	Aluminium sheeting 2mm thick or Aluminium composite material ACM sheeting - 3mm Thick fixed with Micro Prismatic (HIP) Type IV sheeting including 2% towards cost of drilling holes, nuts, bolts etc.and signs as applicable (lettering included) (PWD CSR 2023-24, Vol:3, P.NO.A-9, I No: 07)	Sqm	72.00	5124.00	Rupees Five Thousand One Hundred Twenty Four Only	368928.00

V. S. PATIL
CLASS-I CIVIL CONTRACTOR
DHARWAD.

SNo.	Item Code	Item Name	Unit	Estimate Quantity	After Negotiation Final Quoted Rate in Figure	Amount in Words	Amount in Rs.
78	PWD SR V 5 Page No 201 Item No 16 40	Providing and constructing of Machinehole chambers conical in shape at top with CC 1:3 6 foundation using 40mm and down size graded metal of approved quality and with an offset of 0 15m alround the chamber and brick masonry in C M 1:4 plaster with bricks of approved quality and CM plaster 1:3 proportion 12mm thick inside and outside except for the conical surface outside where the thickness of plaster shall be 20 mm thick, with 1 to 6 slope in the concrete towards the central drain, finished smooth and fixing of pipes in CC 1 2:4 with graded metal of 20 mm and down size including Providing and fixing SFRC Machinehole frame and cover confoming to IS 12592(Part-I) 1988 & IS 12592(Part-II) 1991 with latest amendments in CC 1:2:4, Providing and fixing of plastic foot steps staggered at 30cms apart as directed, watering, curing,barricading, danger lighting, pouring tar over M H frame and cover, cost of tar, shoring, strutting, dewatering, engraving Machinehole No on the inner and outer conical surface etc as per the drawing with all lead and lift for various diameters and depths noted below With Table Moulded Bricks & Medium Duty cover and frame For 1 2m dia Constructing Table Moulded Bricks Machinehole 1 2 m internal dia , 3 0 M depth & Medium duty SFRC cover & frame (Vol-5 Page No 201 & Item No 16 40)	Each	3 00	78325 00	Rupees Seventy Eight Thousand Three Hundred Twenty Five Only	234975 00
79	PWD SR V 5 Page No 201 Item No 16 40	Providing and constructing of Machinehole chambers conical in shape at top with CC 1:3:6 foundation using 40mm and down size graded metal of approved quality and with an offset of 0 15m alround the chamber and brick masonry in C M 1:4 plaster with bricks of approved quality and CM plaster 1:3 proportion 12mm thick inside and outside except for the conical surface outside where the thickness of plaster shall be 20 mm thick, with 1 to 6 slope in the concrete towards the central drain, finished smooth and fixing of pipes in CC 1:2:4 with graded metal of 20 mm and down size including Providing and fixing SFRC Machinehole frame and cover confoming to IS 12592(Part-I): 1988 & IS 12592(Part-II) 1991 with latest amendments in CC 1:2:4, Providing and fixing of plastic foot steps staggered at 30cms apart as directed, watering, curing,barricading, danger lighting, pouring tar over M H frame and cover, cost of tar, shoring, strutting, dewatering, engraving Machinehole No on the inner and outer conical surface etc as per the drawing with all lead and lift for various diameters and depths noted below With Table Moulded Bricks & Medium Duty cover and frame For 1 2m dia Constructing Table Moulded Bricks Machinehole 1 2 m internal dia , 3 0 M depth & Medium duty SFRC cover & frame (Vol-5 Page No 201 & Item No 16 40)	Each	19 00	78326 00	Rupees Seventy Eight Thousand Three Hundred Twenty Six Only	1488194 00
	PWD SR V 5 Page No 201 Item No 16 40	Providing and constructing of Machinehole chambers conical in shape at top with CC 1:3:6 foundation using 40mm and down size graded metal of approved quality and with an offset of 0 15m alround the chamber and brick masonry in C M 1:4 plaster with bricks of approved quality and CM plaster 1:3 proportion 12mm thick inside and outside except for the conical surface outside where the thickness of plaster shall be 20 mm thick, with 1 to 6 slope in the concrete towards the central drain, finished smooth and fixing of pipes in CC 1:2:4 with graded metal of 20 mm and down size including Providing and fixing SFRC Machinehole frame and cover confoming to IS 12592(Part-I): 1988 & IS 12592(Part-II) :1991 with latest amendments in CC 1:2:4, Providing and fixing of plastic foot steps staggered at 30cms apart as directed, watering, curing,barricading, danger lighting, pouring tar over M H frame and cover, cost of tar, shoring, strutting, dewatering, engraving Machinehole No on the inner and outer conical surface etc as per the drawing with all lead and lift for various diameters and depths noted below With Table Moulded Bricks & Medium Duty cover and frame For 1 2m dia Constructing Table Moulded BricksMachinehole 1 2 m internal dia 2 00M depth & Medium duty SFRC cover	Each	34 00	51192 00	Rupees Fifty One Thousand One Hundred Ninety Two Only	1740528 00

V.S. PATIL
CLASS-I CIVIL CONTRACTOR
DHARWAD.

SNo.	Item Code	Item Name	Unit	Estimate Quantity	After Negotiation Final Quoted Rate in Figure	Amount in Words	Amount in Rs.
	PWD SR V 5 Page No 201 Item No 16.46.1	Providing and constructing of Machinehole chambers conical in shape at top with CC 1:3:6 foundation using 40mm and down size graded metal of approved quality and with an offset of 0.15m alround the chamber and brick masonry in C.M 1:4 plaster with bricks of approved quality and CM plaster 1:3 proportion 12mm thick inside and outside except for the conical surface outside where the thickness of plaster shall be 20 mm thick, with 1 to 6 slope in the concrete towards the central drain, finished smooth and fixing of pipes in CC 1:2:4 with graded metal of 20 mm and down size including Providing and fixing SFRC Machinehole frame and cover confoming to IS 12592(Part-I) 1988 & IS 12592(Part-II) 1991 with latest amendments in CC 1:2:4, Providing and fixing of plastic foot steps staggered at 30cms apart as directed, watering, curing,barricading, danger lighting, pouring tar over M.H. frame and cover, cost of tar, shoring, strutting, dewatering, engraving Machinehole No. on the inner and outer conical surface etc. as per the drawing with all lead and lift for various diameters and depths noted below Constructing Table Moulded Bricks Machinehole 1.2 m internal dia. , 1.2 M depth & Heavy duty SFRC cover & frame (Vol-5 Page No.201 & Item No.16.40)	Each	18.00	32420.00	Rupees Thirty Two Thousand Four Hundred Twenty Only	583560.00
	PWD SR V 5 Page No 201 Item No 16.46.1	Providing and constructing of Machinehole chambers conical in shape at top with CC 1:3:6 foundation using 40mm and down size graded metal of approved quality and with an offset of 0.15m alround the chamber and brick masonry in C.M 1:4 plaster with bricks of approved quality and CM plaster 1:3 proportion 12mm thick inside and outside except for the conical surface outside where the thickness of plaster shall be 20 mm thick, with 1 to 6 slope in the concrete towards the central drain, finished smooth and fixing of pipes in CC 1:2:4 with graded metal of 20 mm and down size including Providing and fixing SFRC Machinehole frame and cover confoming to IS 12592(Part-I) 1988 & IS 12592(Part-II) 1991 with latest amendments in CC 1:2:4, Providing and fixing of plastic foot steps staggered at 30cms apart as directed, watering, curing,barricading, danger lighting, pouring tar over M.H. frame and cover, cost of tar, shoring, strutting, dewatering, engraving Machinehole No. on the inner and outer conical surface etc. as per the drawing with all lead and lift for various diameters and depths noted below Constructing Table Moulded Bricks Machinehole 1.2 m internal dia. , 1.5 M depth & Heavy duty SFRC cover & frame (Vol-5 Page No.201 & Item No.16.40)	Each	25.00	39728.00	Rupees Thirty Nine Thousand Seven Hundred Twenty Eight Only	993200.00
	PWD SR V 5 Page No 201 Item No 16.46.1	Providing and constructing of Machinehole chambers conical in shape at top with CC 1:3:6 foundation using 40mm and down size graded metal of approved quality and with an offset of 0.15m alround the chamber and brick masonry in C.M 1:4 plaster with bricks of approved quality and CM plaster 1:3 proportion 12mm thick inside and outside except for the conical surface outside where the thickness of plaster shall be 20 mm thick, with 1 to 6 slope in the concrete towards the central drain, finished smooth and fixing of pipes in CC 1:2:4 with graded metal of 20 mm and down size including Providing and fixing SFRC Machinehole frame and cover confoming to IS 12592(Part-I) 1988 & IS 12592(Part-II) 1991 with latest amendments in CC 1:2:4, Providing and fixing of plastic foot steps staggered at 30cms apart as directed, watering, curing,barricading, danger lighting, pouring tar over M.H. frame and cover, cost of tar, shoring, strutting, dewatering, engraving Machinehole No. on the inner and outer conical surface etc. as per the drawing with all lead and lift for various diameters and depths noted below Constructing Table Moulded Bricks Machinehole 1.2 m internal dia. , 1.8 M depth & Heavy duty SFRC cover & frame (Vol-5 Page No.201 & Item No.16.46.1)	Each	14.00	47037.00	Rupees Forty Seven Thousand Thirty Seven Only	658518.00

V. S. PATIL
CLASS-I CIVIL CONTRACTOR
DHARWAD.

Seal and Singnature of Contractor

The Executive Engineer, DMA

SNo.	Item Code	Item Name	Unit	Estimate Quantity	After Negotiation Final Quoted Rate in Figure	Amount in Words	Amount in Rs.
	PWD SR V 5 Page No 201 Item No 16 46 1	Providing and constructing of Machinehole chambers conical in shape at top with CC 1:3:6 foundation using 40mm and down size graded metal of approved quality and with an offset of 0 15m alround the chamber and brick masonry in C M 1:4 plaster with bricks of approved quality and CM plaster 1:3 proportion 12mm thick inside and outside except for the conical surface outside where the thickness of plaster shall be 20 mm thick, with 1 to 6 slope in the concrete towards the central drain, finished smooth and fixing of pipes in CC 1:2:4 with graded metal of 20 mm and down size including Providing and fixing SFRC Machinehole frame and cover confoming to IS 12592(Part-I): 1988 & IS 12592(Part-II) 1991 with latest amendments in CC 1:2:4, Providing and fixing of plastic foot steps staggered at 30cms apart as directed, watering, curing,barricading, danger lighting, pouring tar over M H frame and cover, cost of tar, shoring, strutting, dewatering, engraving Machinehole No on the inner and outer conical surface etc as per the drawing with all lead and lift for various diameters and depths noted below Constructing Table Moulded Bricks Machinehole 1.2 m internal dia , 1 1 M depth & Heavy duty SFRC cover & frame (Vol-5 Page No 201 & Item No 16 46 1)	Each	15 00	30000 00	Rupees Thirty Thousand Only	450000 00
	PWD SR V1 Page No 16 Item No 2 4 2	Providing and laying in position Cement Concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necessary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specificatio M20 Design Mix Using 20 mm nominal size graded crushed coarse aggregates CSR 2023-24 (Vol-1 Page No 16 & Item No 2 4 2)	Cum	4 80	10200 00	Rupees Ten Thousand Two Hundred Only	48960 00
	PWD SR V1 Page No 16 Item No 2 4 2	Providing and laying in position Cement Concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necessary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications M25 Design Mix Using 20 mm nominal size graded crushed coarse aggregates CSR 2023-24 (Vol-1 Page No 16 & Item No 2 4 3)	Cum	22 36	8378 00	Rupees Eight Thousand Three Hundred Seventy Eight Only	187332 08
	PWD SR V1 Page No 16 Item No 2 4 2	Providing and laying in position Cement Concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necessary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specificatio M20 Design Mix Using 20 mm nominal size graded crushed coarse aggregates CSR 2023-24 (Vol-1 Page No 16 & Item No 2 4 2)	Cum	358 13	8361 00	Rupees Eight Thousand Three Hundred Sixty One Only	2994324 93

V S. PATIL
CLASS-I CIVIL CONTRACTOR
DHARWAD.

Seal and Singnature of Contractor

The Executive Engineer, DMA

SNo.	Item Code	Item Name	Unit	Estimate Quantity	After Negotiation Final Quoted Rate in Figure	Amount in Words	Amount in Rs.
	PWD SR V1 Page No 16 Item No 2.4.3	Providing and laying in position Cement Concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necessary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. M25 Design Mix Using 20 mm nominal size graded crushed coarse aggregates. CSR 2023-24 (Vol-1 Page No.16 & Item No.2.4.3).	Cum	8.10	9406.00	Rupees Nine Thousand Four Hundred Six Only	76188.60
	PWD SR V1 Page No 16 Item No 2.4.3	Providing and laying in position Cement Concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necessary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. M25 Design Mix Using 20 mm nominal size graded crushed coarse aggregates. CSR 2023-24 (Vol-1 Page No.16 & Item No.2.4.3).	Cum	120.61	8378.00	Rupees Eight Thousand Three Hundred Seventy Eight Only	1010470.58
	PWD SR V6 & Item No.32.05	1.1 kV, XLPE or Heat resistant PVC insulated, PVC exutruted Inner Seath Armoured LTUG Cable as per IS-1554 (Part- 1) or IS-7098 Part-1, Armouring strip thickness and resistivity as per IS-3975 16 Sqmm, 4 Core, (11 GI Strips - 4 x 0.8 mm) Material code-287206 SR 2023-2024 (Vol-6 & Item No.32.05)	Km	1.50	156306.00	Rupees One Lakh(s) Fifty Six Thousand Three Hundred Six Only	234459.00
	PWD SR V6 & Item No.68.16	Automatic Switch for Street Light Material code-612645 CSR 2023-2024 (Vol-6 & Item No.68.16)	No	2.00	2537.00	Rupees Two Thousand Five Hundred Thirty Seven Only	5074.00
	PWD SR V6 & Item No.68.18	Street light metering box made of MS sheet steel with Clamp, Material Code-358012 CSR 2023-24 (Vol-6 & Item No.68.18)	No	50.00	1620.00	Rupees One Thousand Six Hundred Twenty Only	81000.00
	PWD SR V6 Item No 45.01	11 kV, Jointing & Cable Termination Kit as per IS-13573 Heat Shrinkable Type Transition Jointing Kit for XLPE Cable 3x95 Sqmm	Set	1.00	11290.00	Rupees Eleven Thousand Two Hundred Ninety Only	11290.00
	PWD SR V6 Page No. 10 Item No 4.2.7	Fabricating, supplying and erection of . ms long hot dip Galvanized Octagonal hot dip Pole with BSEN 10025 grade S 355 JO steel plate for shaft, IS 2062 for base plate with door opening arrangements, including suitable boards, Bakelite sheet and MCBs as per IS specifications suitable to withstand the wind speed of 47 m/s for .m Pole in single section and single joint welded as per IS 9595/IS10178AWS having dimensions bottom . mm , top. mm with 3 mm thick, suitable base plate and 4Nos of . long J bolts along with template and the Pole shall be hot dip galvanized in single dipping with not less than 65micron as per ASTM-A123 and 153 etc., (excluding foundation) as per drawing appended. 9 m - Top 70 mm and Bottom 155 mm dia CSR 2023-24 (Vol-6 Page No.10 & Item No.4.2.7)	No	50.00	21488.00	Rupees Twenty One Thousand Four Hundred Eighty Eight Only	1074400.00
	PWD SR V6 Page No. 10 Item No 4.2.7	Supplying, and fixing of Hot dip Galvanized M.S Bracket suitable for out door luminaries and mounted on Octagonal pole using necessary bolts, nuts etc., complete. Single Arm Bracket with 1000 mm Standard 40/50 mm dia. CSR 2023-24 (Vol-6 Page No.12 & Item No.4.6.1).	No	50.00	2319.00	Rupees Two Thousand Three Hundred Nineteen Only	115950.00
	PWD SR V6 Page No 13 & Item No 5.7.3	Supplying & fixing of Porcelain fuse channel with cut out on existing wooden/panel using necessary nuts, bolts and washers 63 A CSR 2023-2024 (Vol-6 & Item No 5.7.3)	No	2.00	430.00	Rupees Four Hundred Thirty Only	860.00

V.S. PATIL
CLASS-I CIVIL CONTRACTOR
DHARWAD.

Seal and Signature of Contractor

The Executive Engineer, DMA

SNo.	Item Code	Item Name	Unit	Estimate Quantity	After Negotiation Final Quoted Rate in Figure	Amount in Words	Amount in Rs.
	PWD SR V6 Page No 15 & Item No 5 15 1	Supplying and fixing Moulded Case Circuit Breaker (MCCB) over the existing wood/panel board using necessary screws, bolts, nuts, necessary phase separators, handle and wiring complete Protection of Overload and Short circuitwith adjustable thermal magnetic release, Micro processor release shall have Earth Fault as per IS/IEC 60947-2 (Icu=100% Ics). In 4P MCCB, all Poles should have protection for Short-Circcuit/Over Load For Microprocessor MCCBS Facility for segregating Priority and Non-Priority loads must be available in the MCCB MCCB shall be provided with double insulation (insulation between front cover and internal power circuits to avoid any accidental contact with live current carrying path with the front cover open). Multi-pole breakers shall be designed to break all the poles simultaneously and they shall have a single mechanism. THREE Pole 100 A 25 kA CSR 2023-2024 (Vol-6 Page No 15 & Item No 5 15 1)	No	2 00	6706 00	Rupees Six Thousand Seven Hundred Six Only	13412 00
	PWD SR V6 Page No 16 & Item No 5 18 6	Supplying & fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898. 50-63 A DP CSR 2023-2024 (Vol-6 Page No 16 & Item No 5 18 6)	No	2 00	1200 00	Rupees One Thousand Two Hundred Only	2400 00
	PWD SR V6 Page No 18 & Item No 5 3	Supplying, fixing and wiring Electronic Trivector Meter (ETV) 5 to 20A single phase Class-1 Accuracy with Temper Proof Energy Meter CSR 2023-2024 (Vol-6 Page No 18 & Item No 5 3)	No	2 00	1520 00	Rupees One Thousand Five Hundred Twenty Only	3040 00
	PWD SR V6 Page No 19 & Item No 5 40 2	Supplying A rated 3phase with neutral bus bar using required capacity electrolytic aluminium strips covered with heat shrinkable coloured PVC sleeve, mounted on phenolic/FRP/DMC insulator which are mounted on powder coated 40x6mm M S flat frame work in existing panel board. The bus bar shall have suitable holes for termination of incoming and outgoing cables as per IS specification with necessary bolts, nuts and washers etc., complete 250 A 4 x 30 x 10 mm Aluminium Strips CSR 2023-2024 (Vol-6 Page No 19 & Item No 5 40 2)	No	1 00	3785 00	Rupees Three Thousand Seven Hundred Eighty Five Only	3785 00
	PWD SR V6 Page No 20 & Item No 5 47	Supplying and fixing Microprocessor based Electronic timer (without contactor, Din Mounting using necessary bolts, nuts and washers etc ,) 3-120sec setting CSR 2023-2024 (Vol-6 Page No 20 & Item No 5 47)	No	2 00	2551 00	Rupees Two Thousand Five Hundred Fifty One Only	5102 00
	PWD SR V6 Page No 4 & Item No 2 3 3	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100V grade, multistrand copper wire with low conductor resistance single core in open or concealed system of wiring with specified IS-694:2010 2 5 mm2 CSR 2023-2024 (Vol-6 Page No 4 & Item No 2 3 3)	m	1000 00	46 00	Rupees Forty Six Only	46000 00

V. S. PATIL
CLASS-I CIVIL CONTRACTOR
DHARWAD.

Seal and Singnature of Contractor

The Executive Engineer, DMA

SNo.	Item Code	Item Name	Unit	Estimate Quantity	After Negotiation Final Quoted Rate in Figure	Amount in Words	Amount in Rs.
	PWD SR V6 Page No 44 Item No 11 8 3	Supply of LED Streetlight luminaire with pressure die cast aluminium housing body for optimal thermal dissipation Lamp compartment comprising of anti glare clear diffuser with Injection moulded polycarbonate material, delivering superior light output Rated life Burning Hrs 50000 hr @ Lumen Maintenance of 70%, maximum light intensity should be between 60 degrees to 70 degrees. CCT 5500K, IP66 optical and electrical compartment & impact resistance of complete luminaire IK08 Power Factor 0 9 with mains, Surge Protection Min 5KV along with Over voltage/ Overload, short circuit/ miss-wiring protection. Compatible for pole mounting with outer dia of 40mm to 50mm. Universal Voltage driver to operate wide voltage range from 100V to 270V 50/60Hz application. Compliance to IS 10322/IEC 60598, LM 79 & LM 80 Adherence with RoHS. UL approved MCPCB. Top access street light with single screw to ensure ease of maintenance at the sight site location with minimized minimal tools. LED Light fixture with W System Power consumption. LED Efficiency130lm/w, nominal CRI 75. Luminaire manufacturer should have in-house facility accredited by NABL/CPRI & any Government certified agency & Design & Development facility certified by ISO 9001:2008. Housing with supplier word mark /name shall be Engraved / Embossing on the die cast housing/ Body part. Warranty of 2 Years against any manufacturing defect working under standard electrical conditions as mentioned above should be given by LED manufacturer & Cree/Nichia/ Lumileds/Osram make LED Source. LED Streetlight 70W CSR 2023-24 (Vol-6 Page No.44 & Item No.11 8.3	No	50.00	6603.00	Rupees Six Thousand Six Hundred Three Only	330150.00
	PWD SR V6 Page No 53 & Item No 12 56	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C. cutouts and other equipment's on the meter board using 40 mm dia 2 90 mm thick GI pipe 2.5m long buried in a pit . The pit should be filled with equal proportion of salt and charcoal 150 mm allround the pipe to complete depth. The connection from the pipe to the conduit etc., is to be established through GI wire of size as per ISI specification 7.3.3. of IS 732 using 12 mm dia bolts, nuts, washers and check nuts etc., the pipe shall have 16 through holes of 12 mm dia CSR 2023-2024 (Vol-6 Page No.53 & Item No.12.56)	No	2.00	3867.00	Rupees Three Thousand Eight Hundred Sixty Seven Only	7734.00
						Total Contract Amount in Rs.	428590237.37

V. S. PATIL
CLASS-1 CIVIL CONTRACTOR
DHARWAD.